

LEASE NAME Burgess "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #4

990 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 21 TWP. 31S RGE. 8 W

COUNTY Harper

Date Well Completed 3-17-84

Plugging Commenced 7-14-93

Plugging Completed 7-15-93

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500

PHONE#(316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-13-93 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippi Depth to Top 4370 Bottom 4380 T.D. 4380

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	264	8-5/8"	264'	None
		0	4370	5-1/2"	4370'	2816.34'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged and abandon using 60/40 Pozmix, 4% gel. Set 1st plug @ 1359.00' w/30 sks cement; 2nd plug @ 929.23' w/30 sks cement; 3rd plug @ 321.45' with cement circulated to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address P. O. Box 781624, Wichita, KS 67278

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation RECEIVED
STATE CORPORATION COMMISSION
7-28-93
JUL 28 1993


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation

(Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500
Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 93

Lorna Leslie Hull
Notary Public

My Commission Expires: 1-11-96