

15-077-00126-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 9 Twp. 31 Rge. 8 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/NW/SE

Lease Owner Globe Construction Company

Lease Name Culver Well No. #1

Office Address 1041 N. Water Street, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 2-25 19 57

Plugging completed 3-1 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4491' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3633'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into TD 4491'.  
Plugging started 2-25-57. Finished 3-1-57.  
Plugged off bottom, with sand back to 4370' and dumped 5 sacks cement with bailer. Shot 5 1/2" casing at 3633'. Pulled pipe out of hole and plugged well with heavy mud to 200' and set permanent rock bridge. Dumped 25 sacks cement. Filled hole, set rock bridge and dumped 10 sacks cement for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of March, 1957.

My commission expires November 8, 1960.

[Signature] Notary Public.

PLUGGING  
FILE SEC. 9 T. 31 R. 8W  
BOOK PAGE 140 LINE 44

RECEIVED  
STATE CORP  
3-7-57

ROTARY DRILLING LOG

COMPANY: E. C. Stewart, et al

Rotary Drilling Commenced 1/11/54

LOCATION: Culver #1 NW NW SE  
Sec. 9-31S-8W Harper County, Kansas

Rotary Drilling Completed 1/18/54

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 160' of 8 5/8" surface casing cemented  
with 150 sacks cement circulated  
  
114 jts of 5 1/2" 15.5# J-55 casing set  
at 4307' and cemented with 100 sacks  
cement.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Red Rock	160	Circ. for samples @ 3737
Red Bed & shale	985	" " " " 3965
Salt & Shale	1045	" " " " 4408
Shale	1310	
Anhydrite	1325	
Shale & shells	1520	S.L.M. 2805 - O.K.
Lime	1785	S.L.M. 4310 - O.K.
Lime & shale	1930	
Lime	2250	Slope Test @ 2805 - 0° off
Lime & shale	2400	Slope Test @ 4310 - 0° off
Shale	2645	
Shale & lime	2805	
Lime shale	2975	
Lime & shale	3150	
Lime	4037	
Lime & shale	4065	
Lime	4172	
Shale & lime	4206	
Lime	4310	
Shale & lime	4350	
Lime	4395	
Lime & shale	4398	
Mississippi	4408 RTD.	

RECEIVED  
STATE OF KANSAS  
FEBRUARY 15 1954  
2-15-54  
CONSERVATION DIVISION  
Wichita, Kansas

No. 400354

The undersigned, C. H. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PLUGGING  
SEC. 9 T. 31. S. 8W.  
BOOK PAGE 140 LINE 44

PICKRELL DRILLING COMPANY  
By C. H. Sebitts  
Attorney-in-Fact

STATE OF KANSAS,  
COUNTY OF SEDGWICK } ss.:

On this 26th day of January, 1954, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. H. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

Ethel Zimmerman  
Notary Public

My commission expires: January 28, 1957