


15-077-00134-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 9 Twp. 31S Rge. 8W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW/NW/NE
Lease Owner Mull Drilling Co. Inc.
Lease Name Warren Well No. 1
Office Address 6405 E. Kellogg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed Yes 19
Application for plugging approved Yes 19
Plugging commenced 1-21 19 57
Plugging completed 1-28 19 57
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4421' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,035'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Measured into TD 4421.
Plugging started 1-21-57. Finished 1-28-57.
Plugged off bottom with sand back to 4380' and dumped 5 sacks cement with bailer and shot 5 1/2" casing at 3,035'. Pulled pipe out of hole and plugged well with heavy mud to 200' and set permanent rock bridge. Dumped 25 sacks cement. Filled hole with heavy mud to 35' and mixed 10 sacks cement for cap on well.

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1957
2-2-57

CONSERVATION DIVISION
Wichita, KS

Name of Plugging Contractor J.O. Forbes (If additional description is necessary, use BACK of this sheet)
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of January, 1957.

My commission expires November 8, 1960. Notary Public.

PLUGGING
FILE SEC 9 T.31 R.8W
BOOK PAGE 135 LI E 26

15-077-0034-0000

ROTARY DRILLING LOG

COMPANY: Frank Murrell, operator
Wichita, Kansas

Rotary Drilling Commenced 2/9/54

LOCATION: Section 9-31-8
Sarger County, Kansas

Rotary Drilling Completed 2/25/54

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD:

5 Jts of 6 5/8" 24 J-55 cased. casing set at 160' and cemented with 175 sacks cement circulated.


219 Jts of 5 1/2" 15.5 casing set at 4420' cemented with 100 sacks cement.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Sand	90	circ. for samples to 4396'
Red Rock	159	
Red clay	345	S.L.S. 2905' - 0.5'
Shale & shells	900	S.L.S. 4222' - 0.5'
Salt shale & shells	1030	
Shale	1330	Slope Test 2905' 0° off
Anhydrite	1350	Slope Test 4222' 0° off
Shale & shells	1645	
Lime	2200	
Lime shale	2430	
Shale	2595	
Shale & lime	2735	
Lime	2960	
Lime & shale	2960	
Lime shale	3120	
Lime	4222	
Lime & shale	4269	
Lime	4320	
Shale	4393	
Miss. Lime	4396	
Chert	4421	

The undersigned, Frank Murrell, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.



PICKRELL DRILLING COMPANY
By [Signature]
Attorney-in-Fact

STATE OF KANSAS,
COUNTY OF SEDGWICK

On this 14th day of March, 19 54, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared Frank Murrell, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

[Signature]
Notary Public

Dated: January 28, 1957