


15-077-10075-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 9 Twp. 31S Rge. 8 (E/W) (W)

Location as "NE/CNW/SW" or footage from lines NW/SW/SW

Lease Owner Mull Drilling Company, Inc.

Lease Name Dresser Well No. #1

Office Address 6105 East Kellogg Street, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 5-9 1957

Plugging completed 5-14 1957

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4437 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,647

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into TD 4437'.
Plugging started 5-9-57. Finished 5-14-57.
Plugged off bottom with sand and dumped 5 sacks cement with bailer.
Shot 5 1/2" casing at 3,647'. Pulled pipe out of hole and plugged well with heavy mud to 200' and set permanent rock bridge. Dumped 20 sacks cement. Filled hole with heavy mud to 35' and mixed 10 sacks for cap on well.

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1957
5-17-57
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
J.O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of May, 1957.

My commission expires November 8, 1960.
Betty S. Edman
Notary Public.

PLUGGING
FILE SEC 9 T. 31 S. 8W
BOOK PAGE 9 LINE 19

Key

ROTARY DRILLERS LOG

COMPANY : Purcell-Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMMENCED: 7-6-55

CONTRACTOR : Purcell-Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 7-18-55

CASING RECORD: 198' of New 8 5/8" Surf. Csg.
cemented with 150 sacks cement

LOCATION: DRESSER #1
NW SW SW of Sec. 9-318-8W
Harper County, Kansas

Set 5 1/2" 15.5# Csg. @ 437'
cemented with 150 sacks cement

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Sandy Clay	20	Sand & Shale	3643
Red Rock and Sand	198	Lime & Shale	4033
Red Bed	287	Lime	4176
Red Bed, Shale & Shells	750	Lime & Shale	4242
Shale & Shells	1200	Lime	4299
Shale & Anhydrite	1350	Lime & Shale	4361
Shale & Lime	1560	Shale & Lime	4424
Lime & Shale	2120	Chert (Miss)	4437 R.T.D.
Shale & Lime	2635		
Lime & Shale	3487		

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Purcell-Mull Drilling Co., Inc.

Paul H. Purcell
_____, SECRETARY

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 21st day of July, 1955.

Ethel Zimmerman

NOTARY PUBLIC

MY COMMISSION EXPIRES: January 28, 1957

APR 25 1957
4-30-57
DIVISION OF OIL AND GAS
STATE OF KANSAS

PLUGGING
FILE SEC 9 T 31 R 8W
BOOK PAGE 9 LINE 19