

API NUMBER 15-077-20,529-0000

LEASE NAME Williams "C"

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 22 TWP. 31S RGE. 8 (E) or (W)

COUNTY Harper

Date Well Completed 11-01-79

Plugging Commenced 10-06-92

Plugging Completed 10-08-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S Main, Suite 500

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-5-92 (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4390

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	249'	8-5/8"	249'	none
		0	4382'	5-1/2"	4382'	3201.33'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 4350' w/2 sacks cement. Plug using 40/60 Pozmix, 4% gel. Set 1st plug @ 1221.89' w/35 sacks; 2nd plug @ 816.84' w/ 35 sacks; 3rd plug @ 331.17' w/ 35 sacks. Plugging complete 10-08-92

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address P. O. Box 781624, Wichita, KS 67278

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500
 Wichita, KS 67202



before me this 15th day of October, 19 92

Deborah Ann Paulus
 Notary Public