

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-077-20,487-0000

LEASE NAME Williams "B"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #2

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 22 TWP. 32S RGE. 8 (S or W)

COUNTY Harper

Date Well Completed 3-19-79

Plugging Commenced 2-12-91

Plugging Completed 2-12-91

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE#( 316 ) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-12-91 (date)

by Steve Van Dieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Miss. Depth to Top \_\_\_\_\_ Bottom T.D. 4405'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	239'	8-5/8"	239'	0
		0	4391'	4-1/2"	4391'	2830'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 4345'. Place 2 sx cement on top of CIBP with Dump bailer. Cut casing @ 2830'. Pull free. Hallibuton plugged using 40-60 Pozmix. 6% gel. Bottom of 1st plug @ 1347' with 35 sacks. 2nd plug @ 915' with 35 sacks. Top plug @ 228', cement to surface with 60 sacks. Job complete @ 5:00 P.M. 2-12-91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500  
Wichita, KS 67202

FEB 14 1991  
2-14-91



Subscribed and sworn to before me this 13th day of February, 1991

[Signature]  
Notary Public

My Commission Expires: 1-8-92