

API NUMBER 15-077.20.495-0000

LEASE NAME Willaims "B"

WELL NUMBER 3

990 Ft. from S Section Line

-2310 Ft. from E Section Line

SEC. 22 TWP. 31 RGE. 8 or (W)

COUNTY Harper

Date Well Completed 11-78

Plugging Commenced 11-3-87

Plugging Completed 11-5-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-18-87 (date)

by Dist. #2 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Mississippian Depth to Top 4407 Bottom 4424 T.D. 4424

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	272	8-5/8"	272'	0
		0	4422	4-1/2"	4422'	2168'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP @ 4375'. 3 sacks cement on top of plug. Cut casing @ 2403', not free.
Cut casing @ 2168' and pull free. Plug 8-5/8" surface casing w/ Halliburton pump truck using 15 sx gel, 3 sx hulls and 100 sx 60-40 poz mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss. 2-4-88

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Roy McCoy

(Address) 110 S. Main, Suite 500, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 88

Deborah Ann Paulus
 Notary Public

My Commission Expires: 18-92

