

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20,515-0000

LEASE NAME Leeper "A"

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 22 TWP. 31S RGE. 8 ~~22~~ or (A)

COUNTY Harper

Date Well Completed 5-31-79

Plugging Commenced 9-18-95

Plugging Completed 9-20-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Mississippian Depth to Top 4409' Bottom 4417' T.D. 4417'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|-------|--------|--------|------------|
| | | 0 | 256' | 8-5/8" | 256' | None |
| | | 0 | 4409' | 4-1/2" | 4409' | 3017' |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Plugged and abandon using 60/40 Pozmix, 4% gel. Set 1st plug @ 1358' w/35 sx; 2nd plug set @ 877' w/35sx; 3rd plug set @ 319' w/100 sx and circulate to surface. Top off w/20 sx. Plugging complete 9-20-95.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License
STATE CORPORATION COMMISSION

Address P. O. Box 781624, Wichita, KS 67226-4003

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
CONSERVATION DIVISION
Wichita, Kansas

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed, the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3017 N. Cypress
Wichita, KS 67226-4003



before me this 9th day of October, 19 95

Deborah Ann Paulius
Notary Public

My Commission Expires: January 8, 1996