

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rush

County. Sec. 35 Twp. 17 Rge. 16 (E) (W)

Location as "NE/CNW&SW&" or footage from lines C E/2 NW/4 NW/4

Lease Owner Carl Lebsack

Lease Name Juno Well No. 1

Office Address Box 479, Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 29, 1955

Application for plugging filed April 29, 1955

Application for plugging approved April 29, 1955

Plugging commenced April 29, 1955

Plugging completed April 29, 1955

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Depth to top Bottom Total Depth of Well 3669 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	1115'	8-5/8"	1115'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'.
Bridged hole at 300'. Ran 20 sacks
cement 300' up. Heavy mud. Bridge
hole at 35', ran 10 sacks cement.
Plug 35' to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Isern Drilling Company
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS COUNTY OF BARTON

I, M. M. Shropshire (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Shropshire

Lyons, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of May, 1955

My commission expires Feb. 10, 1959.

Notary Public.

PLUGGING
FILE SEC 35 T 17 R 16W
BOOK PAGE 116 LINE 2

15-165-19011-0000

WELL LOG

CARL LEBSACK, OWNER - Juno #1
Center E/2 NW/4 NW/4 Section 35, Township 17, Range 16W,
Rush County, Kansas

ELEVATION: 2020 DF

Figures indicate bottom of formation
0 to 75 sandstone-clay

175 shale
495 shale & shells
630 sand
650 shale & shells
725 sand
900 shale & shells
1105 shale & shells
and red rock

PIPE RECORD:

8-5/8" set at 1115'
Cemented with 800 sacks.

1138 Anhydrite
1410 shale & shells
1540 salt
1805 shale & shells
2280 lime & shale
3060 shale & shells
3480 lime & shale
3610 lime
3635 Conglomerate
3656 Arbuckle
3667 Reagan Sand
3669 Granite Wash
3669 Total Rotary
Depth D&A

Rotary Commenced 4-18-55
Completed 4-29-55

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

RECEIVED
5-6-55
MAY 6 1955
KANSAS CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and Sworn to before me this 2nd day of May, 1955.

M. M. Shropshire
George A. Meyer
Notary Public

My commission expires Feb. 10, 1959.

