

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg.  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-165-21653-0000

LEASE NAME Scheck

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 34 TWP. 17 RGE. 16 (7) or (8)

COUNTY Rush

Date Well Completed 5-9-94

Plugging Commenced 6-14-96

Plugging Completed 6-14-96

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Kan.

PHONE (913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Gas

Oil, Gas, O&A, SWO, Input, Water Supply Well)

The plugging proposal was approved on 6-13-96 (date)

By Mr. Lacy (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation L-KC Depth to Top 3471.5' Bottom 3504' T.O. 3564'

show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u> Lansing-Kan. City</u>	<u> Gas &amp; Wtr.</u>	<u> Surface</u>	<u> 1124</u>	<u> 8 5/8"</u>	<u> 1124</u>	<u> None</u>
		<u> Surface</u>	<u> 3599</u>	<u> 4 1/2"</u>	<u> 3599'</u>	<u> 2300'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from feet to feet each set.

Sanded off bottom - shot 4 1/2" casing off at 2300'. Cemented on way out - spotted 5 sx. gel & 1.50 sx. cement at 1100'. Pulled to 600' and spotted 25 sx. Pulled to 40' & spotted 15 sx. - All 60/40 Poz, 6% gel.

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, Kansas


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.

STATE OF KANSAS COUNTY OF Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Kan. 67601



AND SWORN TO before me this 3rd day of Sept, 19 96

Linda K. Pfannenstiel  
Notary Public

My Commission Expires: 2/5/2000

SEP 05 1996