


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Well or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Rush County, Sec. 34 Twp. 17S Rge. 16 (E) (W)
Location as "NE/CN/WHSW" or footage from lines SE SE NE
Lease Owner Frontier Oil Company
Lease Name Brack A#1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/11/73 19
Plugging completed 11/7/73 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 2670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	201	none
				4 1/2"	3409	452'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3040', ran sand to 2950' and ran 3 sacks cement.
Shot pipe at 2294', 1000', 500', 451', pulled pipe. Pumped 2
sacks hulls, 10 sacks gel and 120 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS


STATE OF KANSAS, COUNTY OF RICE
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

Subscribed and Sworn to before me this 12th day of November 1973

Margaret Melcher
Notary Public

My commission expires



15.165-00343-0000

DRILLERS LOG

No. 1 Brack "A"

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 200.77'	CONTRACTOR:	Red Tiger Drilling Co.	SE NE NE
w/140 sx cement	COMMENCED:	April 2, 1964	34-17S-16W
4 1/2" @ 3409'	COMPLETED:	April 14, 1964	Rush Co., Kansas
w/185 sx cement			ELEVATION:
			2003 DF
			2006 RB
TOTAL DEPTH:			
3670'			

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1973

CONSERVATION DIVISION
Wichita, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface	0	205	
Shale & Shells	205	500	
Sand	500	700	
Shale	700	1070	
Anhydrite	1070	1108	
Shale	1108	1230	
Shale, Lime & Shells	1230	1910	
Shale & Lime	1910	2590	
Lime	2590	2805	
Lime & Shale	2805	3014	
Lime	3014	3610	
Granite Wash	3610	3670	

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1973

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 16th day of April, 1964.

Jeann Hollas
Notary Public

My Commission Expires:

5-22-66