


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rush SEC. 11 TWP. 17S RGE. 17W E/W  
Location as in quarters or footage from lines:  
SE NE NW



Lease Owner Frontier Oil Co.  
Lease Name Steitz-Decker Well No. 1  
Office Address 1720 Kansas St. Bank Bldg., Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
Date Well Completed 8-17-62  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 7-7-82  
Plugging completed 7-7-82  
Reason for abandonment of well or producing formation Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation Topeka Depth to top 3084' bottom 3100' T.D. 3752'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	135 sax	0'	208'	8 5/8"	4-4-62	Still in hole
	300 sax	0'	3682'	4 1/2"	4-11-62	Still in hole
Stage Collar seat @ 1223' with 550 sax						

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set. Used pump truck to put fluids in the hole.

The following is a list of fluids used, starting with what went in the hole first:  
50 sax cement, pozmix 50-50-, 4% gel, 3% C.C.; with 2 sax hulls---Approx. out in formation  
10 sax gel-----approximately 2984' to out in formation  
1 sax hull-----approximately 2804' to 2984'  
8 sax Gel-----approximately 1364' to 2804'  
1 4 1/2" plug-----approximately 1364'  
160 sax cement, pozmix 50-50, 4%gel, 3% C.C.-----approximately 0' to 1364'

Pumped in cement @ 500 PSI Maximum Pressure, Shut In Pressure @ 50# PSI.  
Pressured up on back side to 2,000#, and it would not take any fluid.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

George A. Angle (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.



(Signature) \_\_\_\_\_  
1720 Ks St Bk Bldg., Wichita, Ks 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 82

Jean Stocks  
RECEIVED  
STATE CORPORATION COMMISSION Public.

My Commission expires: 5-14-85

JUL 22 1982

15.165-02282000

**DRILLERS LOG**

Steitz No. 1

**CASING RECORD:** 8 5/8" @ 208' w/135 sx cement  
**COMPANY:** Frontier Oil Company  
**DESCRIPTION:** SE NE NW 11-17S-17W Rush County, Kansas  
**CONTRACTOR:** Red Tiger Drilling Co.  
**COMMENCED:** April 3, 1962  
**ELEVATION:** 2065 DF  
**COMPLETED:** April 12, 1962  
**2068 RB**  
**4 1/2" @ 3682' w/300 sx cement**  
**TOTAL DEPTH:** 3752'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod and Clay	0	120	
Shale and Shells	120	208	
Sand, Shale and Shells	208	580	
Shale and Shells	580	620	
Sand	620	880	
Shale, Shells, Redbed	880	1190	
Anhydrite	1190	1228	
Shale and Shells	1228	1955	
Shale and Lime	1955	2265	
Lime, Shale, Sand	2265	2375	
Shale and Shells	2375	2680	
Shale and Lime	2680	3060	
Lime	3060	3220	
Lime and Shale	3220	3295	
Lime	3295	3634	
Lime Chert	3634	3654	
Arbuckle	3654	3661	
Lime	3661	3720	
Lime and Sand	3720	3752	


I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

*George A. Angle*  
George A. Angle

Subscribed and sworn to before me this 14th day of May, 1962.

*Mahmud Head*  
Notary Public



My Commission Expires:

11-17-62

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 21 1962  
CONSERVATION DIVISION  
Wichita, Kansas