

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20,945-0000

LEASE NAME Leeper "A"

WELL NUMBER #2

660 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 23 TWP. 31S RGE. 8 or (W)

COUNTY Harper

Date Well Completed 10-23-83

Plugging Commenced 6-1-90

Plugging Completed 6-15-90

#2

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well loc. attached? _____

Producing Formation Mississippian Depth to Top 4348 Bottom 4358 T.D. 4358

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	254	0
				5-1/2"	4348	2880'

RECEIVED
STATE CORPORATION COMMISSION

JUL - 9 1990
7-9-90

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 4298'. Place 2 sx cement on CIBP w/ dump bailer. Load casing with water. Cut off 5-1/2" casing @ 2880'. Set bottom of 1st plug @ 1361' w/25 sx. 2nd plug @ 951' w/25sx. Top plug @ 306' circulated to surface with 100 sx. Total 150 sx 40-60 Pozmix, 6% gel by Halliburton. Plugging complete 6-15-90.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John Roger McCoy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Roger McCoy

(Address) 110 S. Main, Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1990



Deborah Ann Paulus
Notary Public

January 8, 1992