

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-077-20,978-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003 ^{6/93}
(owner/company name) (operator's)

ADDRESS 110 South Main Suite 500 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9697

LEASE Burgess "B" WELL# 4 SEC. 21 T. 31S R. 8W (East/West)

N/2 - SW - SW - SPOT LOCATION/OQQQ COUNTY Harper

990 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 264' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4370' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open Hole 4370-4380'

ELEVATION 1561 1571 T.D. 4380' PBDT ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

Note: Estimated TOC by rough calculation @ 3770'
CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP & 2 sacks of cement or dump sand to 4320' & cap with 5 sacks of cement. Shoot & recover casing from calculation according to stretch. Pull casing to 1350' & spot 30 sacks of cement. Pull casing to 900' & spot 30 sacks of cement. Pull casing to 310' & circulate cement to surface. Pull remaining casing from wellbore & top off cement. 60/40 Poz 4% Gel (Orders by Steve VanGieson w/ KCC)
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# (316) 272-1296

ADDRESS City/State Garden City, KS ⁶⁷⁸⁴⁶

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE #
(company name) (contractor's)

ADDRESS P. O. Box 781624, Wichita, KS 67278 PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5-19-93 AUTHORIZED OPERATOR/AGENT: *Daryl Hanson*
(signature)

RECEIVED 3/93
MAY 20 1993
5-20-93
CONSERVATION DIVISION
Wichita, Kansas

2

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 20, 1993

McCoy Petroleum Corporation
110 South Main Suite 500
Wichita KS 67202

Burgess "B" #4
API 15-077-20,9780000
990 FSL 660 FEL
SEC. 21-31S-08W
Harper County

Dear Mr. Daryl Hanson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in dark ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #2 202 W First Suite 304
Wichita KS 67202
(316) 263-8809