

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-077-20,529-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003
(owner/company name) (operator's)

ADDRESS 110 S. Main, Suite 500 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9697

LEASE Williams "C" WELL# 2 SEC. 22 T. 31S R. 8 (East/West)

- S/2- SW - NE SPOT LOCATION/QQQQ COUNTY Harper

 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 249' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4382' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open Hole Completion 4382-4390'

ELEVATION 1581/1571 T.D. 4390' PBDT ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP +/- 4350' & cap with 2 sacks of cement. Pull

casing & shoot according to stretch. Pull casing to 1200', spot 35 sacks of cement. Pull

casing to 800', spot 35 sacks of cement. Pull casing to 300', circulate cement to surface.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# (316) 532-3283

ADDRESS Box 39 City/State Spivey, KS

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE # 30348 COMMISSION
(company name) (contractor's)

ADDRESS P. O. Box 781624 PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR/AGENT

DATE: AUTHORIZED OPERATOR/AGENT:

(signature)

RECEIVED

OCT 19 1992
10-19-92

CONSERVATION DIVISION
WICHITA, KANSAS