

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-077-20,487-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003

ADDRESS 110 South Main/Suite 500/Wichita, Ks 67202 PHONE # (316) 265-9697

LEASE (FARM) Williams "B" WELL NO. 2 WELL LOCATION SE NW SE COUNTY Harper

SEC. 22 TWP. 31S RGE. 8W ~~(S)~~ or (W) TOTAL DEPTH 4405' PLUG BACK TD \_\_\_\_\_

**Check One:**

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 239' CEMENTED WITH 225 SACKS

10.5# K-55 CASING SIZE 4-1/2" SET AT 4391' CEMENTED WITH 150 SACKS

R-3

PERFORATED AT Open Hole 4391 - 4405'

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Set CIBP @ 4350' & 2 sacks cement. Shoot & recover casing according to stretch. Pull casing to base of salt section @ 1360' & spot 35 sacks of cement. Pull casing to top of salt section @ 900' & spot 35 sacks of cement. Pull casing to 289' & circulate cement to surface. Pull remaining casing & top off cement inside 8-5/8" casing.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? X  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl J. Hanson PHONE # (316) 532-5292

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Hayes Well Service LICENSE NO. 5429

ADDRESS Attica, KS PHONE # (316) 254-7204

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *Daryl J. Hanson*  
(Operator or Agent)

DATE: 2-14-91

FEB 14 1991  
2-14-91