

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-077-20,495-~~000~~ (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR McCoy Petroleum Corporation OPERATORS LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202 PHONE # (316) 265-9697

LEASE (FARM) Williams "B" WELL NO. 3 WELL LOCATION NW SW SE COUNTY Harper

SEC. 22 TWP. 31S RGE. 8 or TOTAL DEPTH 4427 PLUG BACK TD 4420

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 272 CEMENTED WITH 225 SACKS

CASING SIZE 4-1/2" SET AT 4426 CEMENTED WITH 150 SACKS

PERFORATED AT 4411 to 4417' (Mississippian)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 4375', in 4-1/2" casing, with

Logging Truck. Put 3 sx cement on top of Plug. Shoot off and pull approximately

3675' of 4-1/2" casing. Plug 8-5/8" surface casing with pump truck using 15 sx of gel,

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson RECEIVED
STATE CORPORATION COMMISSION
11-18-87
NOV 18 1987 PHONE # (316) 532-5452

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Hayes Well Service CONSERVATION DIVISION LICENSE NO. 5429 6/88

ADDRESS Attica, Kansas PHONE # (316) 254-7204

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Daryl Hanson
(Operator or Agent)

DATE: 11-17-87

②

3 sx hulls and 75 sx of Light Cement.



15-877-2075-0000

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

FEB 18 '88

EXPIRES

November 18, 1987
WELL PLUGGING NOTICE

Williams "B" #3
NW SW SE
Sec. 22-31S-08W
Harper County

McCoy Petroleum Corporation
110 S. Main, Ste. 500
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #2 202 W. First, Ste. 300, Wichita, KS 67202 (316) 263-8809