

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-077-20,602-0000 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR McCoy Petroleum Corporation OPERATORS LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202 PHONE # (316) 265-9697

LEASE (FARM) Williams "D" WELL NO. 1 WELL LOCATION S/2 NW NW COUNTY Harper

SEC. 22 TWP. 31S RGE. 8 or (W) TOTAL DEPTH 4433' PLUG BACK TD 4433'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 272 CEMENTED WITH 250 SACKS

CASING SIZE 4-1/2" SET AT 4422 CEMENTED WITH 125 SACKS

PERFORATED AT Open hole 4423-4433'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP in 4-1/2" casing at approximately

4375'. Place 3 sacks cement on top of CIBP. Shoot off and pull approximately 3600' of 4-1/2"

casing. Plug 8-5/8" surface casing with Pump Truck using 15 sx gel, 3 sx hulls and 75 sx

light cement. (If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No Logs IS ACC-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 4-11-88 8:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 532-5292

ADDRESS 1819 Eleanor, Kingman, KS 67068

PLUGGING CONTRACTOR Hayes Well Service LICENSE NO. 5429

ADDRESS Attica, Kansas PHONE # (316) 254-7204

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Roger McCoy
(Operator or Agent)

DATE: 4-5-88

(2)

RECEIVED
STATE CORPORATION COMMISSION
APR - 6 1988
SACKS 4-6-88
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



15-077-20687-0000

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

April 7, 1988

APR 7 '88

WELL PLUGGING NOTICE

EXPIRES

Williams "D" #1
S/2 NW NW
Sec. 22-31S-08W
Harper County

McCoy Petroleum Corporation
110 S. Main, Ste. 500
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #2 202 W. First, Ste. 300, Wichita, KS 67202 (316) 263-8809