

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-069-20,102 ⁰⁰⁰⁰ (of this well). 12/89
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR CHRISTENSEN ENGINEERING OPERATOR'S LICENSE NO. 04762

ADDRESS POB 1937 WICHITA KS 67201 PHONE # (316) 267-8006

LEASE (FARM) Bleumer - Quarry WELL NO. 19-16 WELL LOCATION SE SE SE COUNTY GRAY

SEC. 19 TWP. 267 RGE. 29W ~~(E10E)~~ TOTAL DEPTH 5080 PLUG BACK TD 5026

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 450 CEMENTED WITH 600 SACKS

CASING SIZE 4 1/2 SET AT 5071 CEMENTED WITH 100 SACKS

PERFORATED AT 4994 - 5002

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 50' above Top Perforations, place

4Sx cement on top of Sand Bridge. POH w/4 1/2" CS6, tie on to 8 5/8 and pump

100# HULLS, 105x GEL, 60Sx CEMENT, 105x GEL, 100# HULLS WIPER PLUG & 1405x CEMENT (60140 POZ)

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 20 JUNE 89 / 1330

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

R. Christensen PHONE # (316) 267-8006

ADDRESS POB 1937 WICHITA KS 67201

PLUGGING CONTRACTOR PLAINS INC LICENSE NO. # 4072 11/89

ADDRESS POB 346 Ness City Ks. 67560 PHONE # (913) 798-3995

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]
(Operator or Agent)

DATE: 5 JUNE 1989

JUN 8 1989
CONSERVATION DIVISION
Wichita, Kansas

①

KANSAS

State Geological Survey

WELL COMPLETION REPORT AND
DRILLER'S LOG

WICHITA BRANCH

API No. 15 — 069 — 20,102
County Number

Operator
Samuel Gary Oil Producer

Address
Four Inverness Court East, Englewood, Colorado 80112

Well No. #19-16
Lease Name Bleumer-Ardery

Footage Location
330 feet from (N) (X) line 330 feet from (E) (W) line

Principal Contractor Big "A" Drilling
Geologist James F. Dilts

Spud Date 2/6/81
Date Completed 3/21/81
Total Depth 5080'
P.B.T.D. 5026'


Directional Deviation None
Oil and/or Gas Purchaser Permian Corporation

S. 19 T. 26S R. 29 W

Loc. C SE SE SE

County Gray

640 Acres
N



Elev.: Gr. 2759'

DF 2770' KB 2771'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Secks	Type and percent additives
Surface csg.	12-1/4	8-5/8	240	450	"H"	600	B-4% CaCl
Production csg.	7-7/8	4-1/2	10.50	5071	50/50 pozmix	100	10% salt, 2% gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval
			2	Jet	4994-5002'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8	5024'	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gal. 15% HCL, 10,000 gal. MOD 202, 1000 gal. 15% HCL	4994-5002'

INITIAL PRODUCTION

Date of first production March 21, 1981	Producing method (blowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 47 bbls. Gas 47 MCF Water 0 bbls. Gas-oil ratio 1000 C/PB
Disposition of gas (vented, used on lease or sold) Lease fuel	Producing interval(s) St. Louis

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67208.

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH H. MENLEY CHAIRMAN
MICHAEL KOWALEWSKI COMMISSIONER
MICHAEL WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

SEP 9 1989

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

June 9, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Christensen Engineering
P. O. Box 1937
Wichita, KS 67201

Bleumer-Ardery #19-16
SE SE SE
Sec. 19-26S-29W
Gray County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760