

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-077-21,079-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Graves Drilling Co., Inc. OPERATORS LICENSE NO. 5428
ADDRESS 910 Union Center, Wichita, Kansas 67202 PHONE # (316) 265-7233
LEASE (FARM) Mobil-Smith WELL NO. k WELL LOCATION SW NE NE COUNTY Harper
SEC. 8 TWP. 31S RGE. 8 ~~(E) or (W)~~ TOTAL DEPTH 4500' PLUG BACK TD 4472'

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8-5/8" SET AT 223' CEMENTED WITH 200 SACKS
CASING SIZE 4-1/2" SET AT 4496' CEMENTED WITH 100 SACKS
PERFORATED AT 4407' to 4417', 4449' to 4451', 4454' to 4456 & 4461' to 4464'
CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Blow down & dumped 4 sacks sand & 4 sacks
cement to plug back to 4350'. Ran 4 sacks hulls, 15 sacks gel & 100 sacks common
cement, 3% CC @ 223'. Wooden plug to 0'
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 9, 1985 @ 9:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: RECEIVED
Dennis L. Walker PHONE # (316) 886-3827
STATE CORPORATION COMMISSION

ADDRESS Box 249, Medicine Lodge, Kansas 67104

PLUGGING CONTRACTOR Graves Drilling Co., Inc. LICENSE NO. 5428
CONSERVATION DIVISION
Wichita, Kansas

ADDRESS 910 Union Center, Wichita, Kansas 67202 PHONE # (316) 265-7233

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Betty Brandt
(Operator or Agent)

DATE: May 9, 1985