

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Oden of Red Tiger Drlg. has this
date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: Box 352 Russell, Ks.

Lease Name: Daubert Well No. 1

Location: C NE Sec. 17 Twp. 17 Rge. (E)(W) 17

County: Rush Total Depth 3627' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Oden was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 420° and displace
50 sk cmt thru drill pipe. Heavy mud to 210° set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40° set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Red G. Wasson
Conservation Division Agent