



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Building
WICHITA, KANSAS

RECEIVED
AUG 02 1982
8-2-82
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Dean Boechner of Reach Drlg. Corporation has this date requested permission to plug the following described well:

Operator's Full Name: American Energies Corporation

Complete Address: 575 Fourth Financial Center, Wichita, Ks. 67202

Lease Name: Chase Well No. 1

Location: SW SE SW Sec. 26 Twp. 19 Rge. 29 (E) (W)

County: Lane Total Depth: 4690'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Boechner was instructed to plug the well as follows:

8 5/8"-322' S.P. cuc. w/360 sacks common-2% Gel.-3% Cal.Cl.

Ordered 150 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 1100' w/80 sacks cement

2nd plug @ 350' w/ 40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement

Circulate 10 sacks in rat hole & 10 sacks in mouse hole.

Very truly yours,

Conservation Division Agent