

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-169-00134-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

April 3, 1964

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Arland Bruce of Hollar Oil Company has this date requested permission to plug the following described well:

Mr. Bruce guarantees payment of the plugging fee.

Operator's full Name: Hollar Oil Company

Complete Address: 1117 Wichita Plaza, Wichita, Kansas

Lease Name: Stein Well No. SWD

Location: C SW SW NE Sec. 33 Twp. 16 Rge. 1 (E) (W) X

County Saline Total Depth 3669' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Bruce was instructed to plug the well as follows:

(Unable to get below 900' in 5½" casing that had been circulated with cement to surface.) Push 5½" plug to 900'. Fill hole with sand to 890' and cement hole with 5 sacks.
Fill hole with mud to 145'. Set rock bridge from 145' to 135' and cement hole to surface with 20 sacks cement.

Very truly yours,