



15-169-00127-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

August 16, 1969

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 26 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Bert Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Hollar Oil Company

Complete Address: Box 620, Mc Pherson, Kansas 67460

Lease Name: Stein Well No. 4

Location: C SW SW SW Sec. 33 Twp. 16 Rge. 1 (E) (W) X

County: Saline Total Depth 2615' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

- Fill hole with sand to 2550' and cement with 5 sacks cement.
- Fill hole with mud to 160'. Set rock bridge from 160' to 150' and
- cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock
- bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent