



15-119-20175-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

March 28, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Luke Colter of Apex Drilling Corp. has this date requested permission to plug the following described well:

Operator's Full Name: Grant Oil Company

Complete Address: 9004 W. Warren Dr., Denver, Colorado

Lease Name: Lagerstrom Well No. 1-11

Location: C NE SW NW Sec. 11 Twp. 16 Rge. 4 (E) (W)

County: Saline Total Depth: 3510'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Colter was instructed to plug the well as follows:

8-5/8"-429-350 sacks. Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rathole with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

APR - 5 1981

CONSERVATION DIVISION
WICHITA, KANSAS

Very truly yours,

Conservation Division Agent