



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 11, 1964

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Ray Perera

Complete Address: 100 Laurel Court, McPherson, Kansas

Lease Name: Kelly Well No. 3

Location: NE NE SW Sec. 2 Twp. 16 Rge. 4 (E) (W) X

County Saline Total Depth 3455' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3440' and cement with 5 sacks

Fill hole with mud to 210'. Set rock bridge from 210'

to 200' and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap hole

with 10 sacks cement.

Very truly yours,

Arthur J. Loman
Conservation Division Agent