

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-169-60743-0001

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 26, 1964

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1964

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: American Petrofina Co. of Texas

Complete Address: Box 209, Russell, Kansas

Lease Name: Carlson Well No. 1

Location: NE NE NW Sec. 2 Twp. 16 Rge. 4 (E) (W) X

County Saline Total Depth 3843' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3430' and cement with 5 sacks.

Fill hole with mud to 230'. Set rock bridge from 230' to

220' and cement with 20 sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks

cement.

Very truly yours,  
*William J. Loman*