

State of Kansas



15-169-00626-0060

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 20 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Wassinger of Fender Pipe & Supply Inc. has this  
date requested permission to plug the following described well:

Mr. Wassinger guarantees payment of the plugging fee.

Operator's full Name: Fender Pipe & Supply Inc.

Complete Address: Box 302 Russell, Kansas

Lease Name: Lockstrom Well No. # 8

Location: S/2 S/2 NE Sec. 2 Twp. 16 Rge. 4 (E) (W)


County Saline Total Depth 3444' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Wassinger was instructed to plug the well as follows:

- 8 5/8"-430'-Circulated w/cement. 5 1/2"-3442'-Cemented. Sand hole to 3430'.
- 5 Sax. cement 3430' to 3380'. Mud 3380' to 260'. Bridge 260' to 250'.
- 20 Sax. cement 250' to 190'. Mud 190' to 40'. Bridge 40' to 30'.
- 10 Sax. cement 30' to 0.

Very truly yours,

  
Conservation Division Agent