

To: 1 090209
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-14

API NUMBER 15- 101-21,631-0000

App. NE NE SW, SEC. 3, T. 19 S, R. 30 W/8
2120 feet from S section line
3020 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Bryant "A" Well # 2

Operator: The Dane G. Hansen Trust

County Lane Lane 148.85

Name: The Dane G. Hansen Trust

Address P.O. Box 187

Well Total Depth 4580 feet

Logan, KS 67646

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 224 E. Douglas, Suite 530, Wichita, KS 67202

Company to plug at: Hour: 1:35 p.m. Day: 14 Month: 8 Year: 19 92

Plugging proposal received from Harold Dinkle

(company name) Chief Drilling, Inc. (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2205-24'

1st plug at 2230' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 290' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 14 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement,

2nd plug at 1300' with 80 sx cement, 3rd plug at 650' with 50 sx cement,

4th plug at 290' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have served this plugging.

DATE 9-14-92

Signed [Signature]
(TECHNICIAN)

INV. NO. 26131

RECEIVED
STATE CORPORATION COMMISSION
8-24-92
AUG 24 1992
CONSERVATION DIVISION
Wichita, Kansas