

1 070848

9-10

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,360 ~~0000~~

SW NE NE, SEC. 4, T 19 S, R 30 W4E

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Goering Well # 1

Operator: Pintail Petroleum, Ltd.

County Lane 152.06

Name & Address 412 E. Douglas, Suite One

Well Total Depth 4679 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 10 Month: 9 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 4 1/2" at 4631' w/200 sx cement, PBD 4572', Perfs at 4370-73'

1st plug sand on fish at 2125', sand to 1990', dump 4 sx cement on top,

2nd plug perforate at 1300', set cement retainer and squeeze with 80 sx cement,

3rd plug pump 5 sx gel and 25 sx cement at free point,

4th plug pump 5 sx gel and 25 sx cement at 550', 5th plug pump 5 sx gel and 40 sx cement

at 300', 6th plug pump 10 sx cement at 40-0'. Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6 p.m. Day: 10 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded on fish at 2125', sanded to 1990', dumped 4 sx

cement on top, 2nd plug shot off casing at 1317', ran tubing to 1280' and pumped 80 sx cement

3rd plug layed out tubing, shot at 950' and 820' and pulled casing to 740', pumped 5 sx gel and 40 sx cement, 4th plug pulled tubing to 300' and pumped 5 sx gel and 40 sx cement,

5th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton! Recovered 820' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

observe this plugging.

SEP 13 1990 9-13-90

Signed

Don Johnson

(TECHNICIAN)

INVOICED

DATE: SEP 18 1990

INV. NO. 29351