

1060196

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-20,389-6000  
NW NW NE SEC. 4, T 19 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GOERING WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 149.40

OPERATOR LICENSE # 31627

WELL TOTAL DEPTH 4597 FEET

OPERATOR: WHITETAIL CRUDE, INC. PRODUCTION CSG: SIZE 4 1/2" @ 4561' WITH 200 SX

NAME AND PO BOX 544 SURFACE CASING: SIZE 8 5/8" @ 285' WITH SX

ADDRESS NESS CITY, KS 67560-0544

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 2:15 PM DAY: 22 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES INC (PHONE) 785-798-2300

WERE: PERFS AT 4178-82 & 4138-4140

BOTTOM PLUG PUMP 20 SX CEMENT WITH 100# HULLS. PERFORATED AT 1200'. MIXED 150 SX CEMENT

WENT ON VACUUM. WENT DOWN BACKSIDE WITH 75 SX CEMENT. PRESSURED TO 500# AND HELD.

MIXED 75 SX CEMENT AND 100# HULLS DOWN 4 1/2" AND SHUT IN.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:15 PM DAY: 22 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMPED 20 SX CEMENT WITH 100# HULLS. PERFORATED AT 1200'. MIXED 150 SX

CEMENT WENT ON VACUUM. WENT DOWN BACKSIDE WITH 75 SX CEMENT. PRESSURED TO 500# AND HELD.

MIXED 75 SX CEMENT AND 100# HULLS DOWN 4 1/2" AND SHUT IN.

RECEIVED  
STATE CORPORATION  
3-1-00  
MAR - 1 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) FOR OFFICE USE ONLY  
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

INVOICED  
DATE 3/1/00 SIGNED Michael Maier  
(TECHNICIAN)  
WV. NO. 061346

Michael Maier  
FORM CP-2/3  
(R)