

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20405-00-01
Spot: NENWNE Sec/Twnshp/Rge: 4-19S-30W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: GOERING Well Number: 3
County: LANE Total Vertical Depth: 4580 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS, KS 67560

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 322 WITH 160 SX CMT
Production: Size 4.5 feet: 4539 WITH 200 SX CMT 148.85
Liner: Size feet:

Well Type: EOR UIC Docket No: E26146.1 Date/Time to Plug: 05/08/2001 12:15 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 4230' & 4 SX CMT. TEST 4 1/2 TO 1200'. 1ST PLUG SHOOT @ 1200' SQUEEZE WITH 50 SX CMT & DISPLACE CMT TO FREE POINT. 2ND PLUG SPOT 50 SX CMT @ FREE POINT. 3RD PLUG SPOT 50 SX CMT AT 322'. 4TH PLUG SPOT 10 SX CMT ON TOP.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/08/2001 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4370'. PERFS AT 4287-93, 4394-96, 4364-65. SANDED TO 4000' WITH 4 SX CMT. SHOT AT 1200'. DID NOT COME LOOSE PUMPED 80 SX CMT. SHOT AT 680' PULLED ONE JOINT AND PUMPED 15 SX GEL . PUMPED 50 SX CMT AT 640'. PULLED TO 320' AND PUMPED 40 SX CMT. PULLED REMAINING CASING AND TOPPED OFF WITH 20 SX CMT. HOLE STAYED FULL.

INVOICED
DATE 5-29-01
INV. NO. 2001061845

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 21 2001
5-21-01
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 680' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael J. Maier
(TECHNICIAN)

MAY 15 2001

Form 21-2/3