

1080229

TO: STATE CORPORATION COMMISSION

11-23

API NUMBER 15-101-20,408 SW NE NE SEC. 4 T 19 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME GOERING WELL # 4

TECHNICIAN'S PLUGGING REPORT COUNTY LANE 148.07

OPERATOR LICENSE # 31627 WELL TOTAL DEPTH 4556 FEET

OPERATOR: WHITETAIL CRUDE, INC PRODUCTION CSG: SIZE 4 1/2" @ 4555' WITH 200 SX

NAME AND PO BOX 544 SURFACE CASING: SIZE 8 5/8" @ 322' WITH 150 SX

ADDRESS NESS CITY, KS 67560

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR FRITZLER TRUCKING, INC LICENSE NUMBER NA

ADDRESS PO BOX 544, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 23 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE FRITZLER

(COMPANY NAME) FRITZLER TRUCKING, INC (PHONE) 785-798-3641

WERE: PERFS AT 4370-73, 4392-95, 4446-49, 4394

1ST PLUG SANDED BACK TO 4200' WITH 4 SX CEMENT ON TOP. 2ND PLUG PERFORATE AT 1300', PUMP 90 SX CEMENT AND DISPLACE TO 700' ON VACUUM PUMP 25 SX OF 50# HULLS. DISPLACE TO 900'. 3RD PLUG SHOT 4 1/2 AT 591' PUMP 35 SX CEMENT. 4TH PLUG PULL UP TO 340' PUMP 30 SX CEMENT. 5TH PLUG PULL TO 40' PUMP 20 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 23 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG SANDED BACK TO 4200' WITH 4 SX CEMENT ON TOP. 2ND PLUG LOG-TECH PERFORATED AT 1300', ALLIED PUMPED 90 SX CEMENT DISPLACED TO 700' ON VACUUM PUMPED 25 SX 50# HULLS. DISPLACED TO 900' HELD 300#. 3RD PLUG SHOT 4 1/2" @ 591' PUMPED 35 SX CEMENT SHUT IN AT 300#. 4TH PLUG PULLED UP TO 340' PUMPED 30 SX CEMENT. 5TH PLUG PULLED TO 40' PUMPED 20 SX CEMENT. WELL STANDING AT SURFACE WITH CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 591' OF 4 1/2' CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin P. Strube (TECHNICIAN) FORM CP-2/3

RECEIVED STATE CORPORATION COMMISSION WICHITA, KANSAS 12-2-98

12-4-98 60412