

1060210

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-20,866-0000
NE NE NE SEC. 4, T 19 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GOERING WELL # 6
COUNTY LANE 150.12

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 31627 7/19 WELL TOTAL DEPTH 4619 FEET

OPERATOR: WHITETAIL CRUDE, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4593' WITH 225 SX

NAME AND PO BOX 544 SURFACE CASING: SIZE 8 5/8" @ 288' WITH SX

ADDRESS NESS CITY, KS 67560-0544

RECEIVED
STATE CORPORATION COMMISSION
7-31-00
III 31 2000

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES LICENSE NUMBER 32582 CONSERVATION DIVISION
Wichita, Kansas

ADDRESS PO BOX 466 NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 19 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES (PHONE) 785-798-2300

WERE: PERFS AT 4288-4293, 4364-4444, 4469, 4556-58

1ST PLUG RUN TUBING TO 4530' AND SPOT 35 SX CEMENT AND 100# HULLS. 2ND PLUG PULL TO 2200'
AND SPOT 40 SX CEMENT AND 100# HULLS. 3RD PLUG PULL STRETCH ON CASING, CUT 750' CAME FREE
MIXED 50 SX CEMENT AND 200# HULLS. 4TH PLUG PULL TO 300' AND MIX 40 SX CEMENT. 5TH PLUG
PULL CASING AND TOP OFF WITH 20 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:45 PM DAY: 19 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG RUB TUBING TO 4530' AND SPOT 35 SX CEMENT AND 100# HULLS. 2ND PLUG PULL TO 2200'
AND SPOT 40 SX CEMENT AND 100# HULLS. 3RD PLUG PULL STRETCH ON CASING, CUT AT 750' CAME
FREE MIXED 50 SX CEMENT AND 200# HULLS. 4TH PLUG PULL TO 300' AND MIX 40 SX CEMENT. 5TH
PLUG PULL CASING AND TOP OFF WITH 20 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 760' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED
SIGNED
DATE 8/3/00
INCL NO. 1060302

Michael J. Maier
(TECHNICIAN) FORM CP-2/3