

1 050816

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,317.0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Operator: Chief Drilling Co., Inc.  
Name & Address: 151 North Main, Suite 700  
Wichita, KS 67202

SW SE SE, SEC. 4, T 19 S, R 30 W/E

330 feet from S section line  
990 feet from E section line

Lease Name Bryant "A" Well # 1

County Lane 150.48

Well Total Depth 4630 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 12:00 pm Day: 6 Month: June Year: 19 86

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2885 GL Anhydrite 2209-2234'

1st plug at 2250' with 50 sx cement

2nd plug at 1350' with 80 sx cement

3rd plug at 330' with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:15pm Day: 6 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2234' with 50 sx cement, 2nd plug at 1350' with 80 sx

cement, 3rd plug at 330' with 40 sx cement, 4th plug from 40' to surface with 10 sx

cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse

hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel Mud Vis 45 Weight 9.6 ppg

(If additional description is necessary use BACK of this form.)

observe this plugging.

INVOICED JUN 18 1986

DATE INV. NO. 14127

Signed Richard W. Lacey (TECHNICIAN)