

APR 07 1983

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,764-0000

SW/4, Sec. 20, T 16 S, R 29 W1X

330 feet from X/S section line

330 feet from W1X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name JENNISON Well #B-6

Operator: THUNDERBIRD DRILLING, INC.
Name & Address: P.O. Box 18407
Wichita, KS 67218

County LANE

Well Total Depth 3870 feet #125.76

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor COMPANY TOOLS License Number 5131

Address _____

Company to plug at: Hour: 3:00pm Day: 29 Month: March Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Ed Cook

(company name) THUNDERBIRD (phone) _____

were: to use 50/50 Pozmix, 4% gel, 3% C.C., & spot 1st plug @ 2190' w/50 oil; 2nd plug @ 1080' w/50 oil; 3rd plug @ 390' w/40 oil; 4th plug @ 40' w/solid bridge & 8 5/8 wiper plug, then to surface w/100 oil. Circulate 15 oil in the kathale.

Signed R Barluttan (TECHNICIAN)

Plugging Operations attended by Agent?: All TO MUDDY TO GET TO LOCATION Part None

Operations Completed: Hour: 6:30pm Day: 29 Month: MARCH Year: 1983

ACTUAL PLUGGING REPORT plugged as ordered.

Cementing by Sun Oil well Cementing. Rig is moving 75' east. well plugged because tools lost in hole.

Remarks: Elevation 2763 G.L.
Anhydrite top @ 2169

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 4-15-83
INV. NO. 4045W

Signed R Barluttan (TECHNICIAN)