

8-3-87

1 070381

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,723-0000

SW NE NW, SEC. 22, T 16 S, R 29 W X

4390 feet from S section line

3690 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6420

Lease Name Roberts Well # 1-22

Operator: KRM Petroleum Corporation

County Lane 146.90

Name & Address 1900 Grant, Suite 300

Well Total Depth 4520 feet

Denver, CO 80203

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 3 Month: 8 Year: 19 87

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4513' PBTD 4461'

1st plug sand back to 4280' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 20 sx ATL followed by 130 sx ATL with 400 lbs. hulls mixed in down 5 1/2",

3rd plug pump 20 sx ATL followed by 30 sx ATL with 100 lbs hulls mixed in down 8 5/8".

Plugging Proposal Received by Richard Lacey & Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 3 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dump 5 sx cement on top of sand through bailer,

2nd plug pumped 20 sx ATL followed by 130 sx ATL with 400 lbs. hulls mixed in down 5 1/2".

Maximum pressure 700 psi and shut in 400 psi.

3rd plug pumped 20 sx ATL followed by 30 sx ATL with 100 lbs. hulls mixed in down 8 5/8".

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used ATL by Allied. No recovery. (If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Dan Goodrow (TECHNICIAN)

DATE 8-12-87

INV. NO. 17801

SEP 17 1987

FORM CP-2/3 Rev. 01-84

RECEIVED STATE CORPORATION COMMISSION AUG 10 1987 CONSERVATION DIVISION WICHITA, KANSAS

20