

To: 1070040 11-21
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-101-21,752 0000
E/2 W/2 NW, SEC. 26, T 16 S, R 29 W/E
3960 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860
Operator: Castle Resources Inc.
Name & Address P.O. Box 87
Schoenchen, KS 67667

Lease Name James Well # 3
County Lane 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Discovery Drilling, Inc. License Number 31548
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 2 a.m. Day: 21 Month: 11 Year: 1997

Plugging proposal received from Tom Alm
(company name) Discovery Drilling, Inc. (phone) 785-623-2920

were: to fill hole with heavy mud and spot cement through drill pipe
Elevation 2800' GL
Anhydrite 2208-39'

1st plug at 2240' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,

3rd plug at 250' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

11-26-97

Plugging Proposal Received by Scott Alberg
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45 a.m. Day: 21 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 2240' with 50 sx cement,

2nd plug at 1200' with 80 sx cement,

3rd plug at 250' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

I (~~XXX~~ / did not) observe this plugging.

DATE 12-3-97

Signed _____
(TECHNICIAN)

INV. NO. 49588