

1090148

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,937-0000

NE NE NE , SEC. 29 , T 16 S, R 29

330 feet from N/E section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8758

Lease Name Jennison Well # 1-29

Operator: Raw Energy Corp. of Kansas

County Lane

Name & Address 7200 West 13th, Suite 8

Well Total Depth 4575 148.69 feet

Wichita, KS 67212

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 18611, Wichita, KS 67207

Company to plug at: Hour: 6:30 am Day: 31 Month: March Year: 19 84

Plugging proposal received from Rex Lutes

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2190' with 50 sx cement

2nd plug at 1680' with 50 sx cement

3rd plug at 390' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement
Plugging Proposal Received by *R. Barburton*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 am Day: 31 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement, 2nd plug at 1680' with 50 sx cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton # 748512
(If additional description is necessary, use BACK of this form.)

RECEIVED

INVOICED

DATE 4-4-84

APR 03 1984

Signed *R. Barburton*
(TECHNICIAN)

ENV. NO. 1062 3-31

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84