

1090206

API NUMBER 15- 101-21,003-000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE SE, SEC. 29, T 16 S, R 29 (W)X  
1980 ~~4620~~ FS feet from ~~XXX~~ section line  
660 PEL feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5533

Lease Name Dickey Well # 1

Operator: Arrowhead Petroleum, Inc.

County \_\_\_\_\_ Lane \_\_\_\_\_

Name & Address Box 8287 - Munger Station

Well Total Depth 3965 128.86 feet

Wichita, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Springs Drilling, Inc. License Number 5381

Address Box 8287 - Munger Station, Wichita, KS 67208

Company to plug at: Hour: 11:00 am Day: 24 Month: July Year: 1984

Plugging proposal received from David Bayse

(company name) Big Springs (phone) 316-681-1732

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2220' with 50 sx cement

2nd plug at 1710' with 50 sx cement

3rd plug at 420' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R. B. Barhutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00 pm Day: 24 Month: July Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement, 2nd plug at 1710' with 50  
sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 01 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this FORM)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 8-13-84

Signed R. B. Barhutton  
(TECHNICIAN)

INV. NO. 2960

7-24

SD FORM CP-2/3  
Rev. 01-84