

1 120059

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,275-0000

NE NW SW, SEC. 29, T 16 S, R 29 W/X

2310 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Waddell Well # 1

Operator: Chief Drilling Co., Inc.

County Lane Lane 148.53

Name & Address 151 N. Main, Suite 700

Well Total Depth 4570 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 15 Month: January Year: 19 86

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791  
elevation 2800'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2213-03'

1st plug at 2250' with 50 sx cement 2nd plug at 1450' with 80 sx cement

3rd plug at 800' with 40 sx cement 4th plug at 420' with 40 sx cement  
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole with 15 sx cement

8th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Don C. Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:30 am Day: 15 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2250' with 40 sx cement, 2nd plug at 1450' with 80 sx

cement, 3rd plug at 800' with 40 sx cement, 4th plug at 420' with 40 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with

10 sx cement.

STATE CORPORATION COMMISSION

JAN 27 1986

CONSERVATION DIVISION

Remarks: Cemented by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE FEB 5 1986

Signed Don C. Ubel  
(TECHNICIAN)

INV. NO. 12331

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date Dec. 31, 1985  
month day year

API Number 15- 101-21, 275-0000

OPERATOR: License # 5886  
 Name Chief Drilling Co., Inc.  
 Address 151 N. Main Suite #700  
 City/State/Zip Wichita, Ks. 67202  
 Contact Person Douglas W. Thimesch  
 Phone 316-262-3791

NE NW SW  
2310 Sec. 29 Twp. 16 S, Rg. 29 XX East  
1290 Ft. from South Line of Section  
 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5883  
 Name Warrior Drilling Co. Rig #2  
 City/State Wichita, Ks. 67202

Nearest lease or unit boundary line 330 feet  
 County Lane  
 Lease Name Waddell Well # 1  
 Ground surface elevation Will provide feet MSL  
 Domestic well within 330 feet: 2800 —yes  no  
 Municipal well within one mile: —yes  no  
 Surface pipe by Alternate: 1 2 X  
 Depth to bottom of fresh water 150  
 Depth to bottom of usable water 1200  
 Surface pipe planned to be set 350  
 Projected Total Depth 4550 feet  
 Formation Miss

Well Drilled For: Well Class: Type Equipment:  
 Oil — SWD — Infield  Mud Rotary  
 — Gas — Inj — Pool Ext. — Air Rotary  
 — OWWO — Expl  Wildcat — Cable

If OWWO: old well info as follows:  
 Operator  
 Well Name  
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

CEMENTING cementing will be done immediately upon setting production casing.  
 Date Signature of Operator or Agent Title

For KCC Use:  
 Conductor Pipe Required 350 feet; Minimum Surface Pipe Required 350 feet per Alt. 1   
 This Authorization Expires 7-1-86 Approved By [Signature]

SPUD - 1-8-86 - SD @ 5:00 PM - Allied (365')

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>2250</u>	feet depth with	<u>50</u>	sxs of <u>60-40</u>	post 2% 1886 2% ge
2nd plug @ <u>1700</u>	feet depth with	<u>50</u>	sxs of	
3rd plug @ <u>1450</u>	feet depth with	<u>40</u>	sxs of	CONSERVATION OMS
4th plug @ <u>800</u>	feet depth with	<u>10</u>	sxs of	
5th plug @ <u>40</u>	feet depth with		sxs of	
(2) Rathole with <u>15</u>	feet depth with		sxs of	

PUSHER Manuel Burns  
 TD 4576 FORMATION Miss  
 SURFACE PIPE 5 5/8 @ 371  
 ANHYDRITE 22/3 @ ELEVATION 2600  
 STARTING TIME & DATE 1-8-86  
 COMPLETION TIME & DATE 1-15-86  
 1st PLUG @ 2250 FT. W/ 40 SX  
 2nd PLUG @ 1450 FT. W/ 805 SX  
 3rd PLUG @ 800 FT. W/ 405 SX  
 4th PLUG @ 420 FT. W/ 40 SX  
 RAT HOLE CIRCULATED W/ 15 SX  
 MOUSE HOLE CIRCULATED W/ 10 SX  
 WATER WELL PLUGGED W/ 10 SX  
 CEMENT COMPANY Allied  
 TECHNICIAN [Signature]  
 If D/A - plugging then:  
2250 - 80 s/x  
1450 - 40 s/x  
800 - 40 s/x  
420 - 40 s/x  
 Bridge - 10  
 Rat - 15  
 Mouse - 10  
 No water well (weld)