

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20718-00-00
Spot: CNWNENW Sec/Twnshp/Rge: 29-16S-29W
330 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: JENNISON Well Number: 2
County: LANE Total Vertical Depth: 4516 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

Conductor Pipe: Size feet: 3 1/4 - 77
Surface Casing: Size 8.625 feet: 326 WITH 240 SX CMT
Production: Size 5.5 feet: 4514 WITH 275 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/13/2001 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RICHARD L. WALLGREN, S Company: HANSEN TRUST Phone: (785) 689-4816

Proposed Plugging Method: PUMP 50 SX CMT - 400# HULLS - 18 SX GEL. PERFORATE AT 1250'. PUMP 175 SX CMT. PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/14/2001 1:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4469'. 14 SETS OF PERFS FROM 3842-4468'. PUMPED 400# HULLS - 50 SX CMT - 18 SX GEL & 45 BBL WATER. WELL ON VACUUM. SHUT IN. LOADED HOLE AFTER LETTING SET 1 HOUR WITH 200# ON CASING. SHUT IN. 11/14/01: PRESSURED UP CASING TO 1000#. PERFORATED AT 1250'. LOADED HOLE AND PUMPING INTO @ 650# STARTED DOWN HOLE WITH CMT. PUMPED 175 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 300#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 150 SX CMT. MAXIMUM PRESSURE 200#. SHUT IN WITH 50#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

RECEIVED
NOV 19 2001
KCC WICHITA

INVOICED

NOV 15 2001

DATE 11-20-01
INV. NO. 2002060965

Form 2/3
[Signature]