

To: 1 060181
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-4

API NUMBER 15- 101-21,663-0000
NW NE SW, SEC. 32, T. 16 S, R. 29 W/E
2280 feet from S section line
1740 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3988
Operator: Slawson Exploration Co., Inc.
Name & Address 621 N. Robinson, Ste. 490
Oklahoma City, OK 73102

Lease Name Jennison U Well # 1
County Lane 149.01
Well Total Depth 4585 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling Co. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: _____ Day: 4 Month: 9 Year: 19 93

Plugging proposal received from Greg Davidson
(company name) L.D. Drilling Co. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2232-59'
1st plug at 2300' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,
3rd plug at 400' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 1:30 p.m. Day: 4 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement,
2nd plug at 1250' with 80 sx cement,
3rd plug at 400' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(if additional description is necessary, use BACK of this form)
I (operator) did not observe this plugging.

DATE 9-21-93
INV. NO. 38729

Signed Case Morris
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1993
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3
Rev. 01-84