

1060171

TO: STATE CORPORATION COMMISSION

8-23

API NUMBER 15-101-20,881 ~~(000)~~
NW SE SE SEC. 32, T 16 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

150' 15"

WICHITA, KANSAS 67202 LEASE NAME MADRID WELL # 32-16

TECHNICIAN'S PLUGGING REPORT COUNTY LANE

OPERATOR LICENSE # 5011 WELL TOTAL DEPTH 4620 FEET

OPERATOR: VIKING RESOURCES, INC. PRODUCTION CSG: SIZE 4 1/2" @ 4614' WITH 990 SX

NAME AND 105 S BROADWAY, SUITE 1040 SURFACE CASING: SIZE 8 5/8" @ 245' WITH 200 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 23 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM _____

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 4420-4520 WAS 2 STAGED CEMENT CIRCULATED DV-tool at 2236' w/ 720 SX cmt.

BOTTOM PLUG PUMP 40 SX CEMENT WITH 200# HULLS. GEL SPACER TO ANHYDRITE THEN 160 SX CEMENT

DOWN CASING. PRESSURED TO 800#. SHUT IN WITH 700#. WENT DOWN BACKSIDE WITH 10 SX CEMENT

PRESSURED TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 23 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT _____

BOTTOM PLUG PUMP 40 SX CEMENT WITH 200# HULLS. GEL SPACER TO ANHYDRITE THEN 160 SX

CEMENT DOWN CASING. PRESSURED TO 800#. SHUT IN WITH 700#. WENT DOWN BACKSIDE WITH 10

SX CEMENT. PRESSURED TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. 09-07-99

INVOICED

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 9-16-99

SIGNED Michael J. Maier (TECHNICIAN) FORM CP-2/3

TEL. NO. 605-38

(Handwritten signature and circled number 2)