

To: 1 030647  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,272 - 0000  
NE NE SE, SEC. 33, 'T 16 S, R 29 W  
2310 feet from S section line  
330 feet from E section line  
Lease Name Schmied Well # 1  
County \_\_\_\_\_ Lane 148.82  
Well Total Depth 4579 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 248

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161  
Operator: Palomino Petroleum  
Name & Address R. R. 5, Box 51-C  
Newton, KS 67114

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DNB Drilling, Inc. License Number 5476  
Address 535 N. Oliver, Wichita, KS 67208

Company to plug at: Hour: 2:00 am Day: 19 Month: January Year: 19 86

Plugging proposal received from Jack Taylor  
(company name) DNB (phone) 316-687-5471

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2805 Est.  
Anhydrite 2232-2253'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne sand with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:45 am Day: 19 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2253' with 50 sx cement, 2nd plug at 925' with 80 sx  
cement, 3rd plug at 280' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 27 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 5 1986  
INV. NO. 12368

Signed Steve Durrant  
(TECHNICIAN)