

To: 1 070384
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

Operator: National Petroleum Reserves, Inc.
Name & Address: 260 North Rock Road, Suite 215
Wichita, KS 67206

7-28-87 263 R

API NUMBER 15- 101-21,398 -0000

SW SW NE, SEC. 36, T 16 S, R 29 W X

2970 feet from S section line

2310 feet from E section line

Lease Name Fuller/Stroup Well # 1

County Lane 150.15

Well Total Depth 4620 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 28 Month: 7 Year: 19 87

Plugging proposal received from Ken Lyle

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2789' Anhydrite 2211-2334'

1st plug at 2310' with 50 sx cement, 2nd plug at 1410' with 80 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:15 a.m. Day: 28 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2310' with 50 sx cement,

2nd plug at 1410' with 80 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-12-87

Signed Dan Gordon (TECHNICIAN)

INV. NO. 17802

7-28

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1987
CONSERVATION DIVISION
Wichita, Kansas