

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1962
CONSERVATION DIVISION

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Saline
Location: SW- NE- SE Sec. 2 Twp. 16 Rge. 4 (~~EX~~) (W) _____
Name of Field: Lindsborg Total Depth: 3444'

I have this date completed supervision of plugging of:

Lease Name: Sandberg Well No. 2

Operator's Full Name: John O. Farmer, Inc.

Complete Address: P.O. Box 352 Russell, Kansas.

Plugging Contractor Ace Pipe Pulling Co.

Address: P.O. Box 304 Great Bend Kansas. License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4:PM Day 25 Month I Year 62

The above well was plugged as follows:

Felled hole w/ sand from T.D. 3444' back to 3430' ran 5 sax cement w/ dump bailer.
Shot off and pulled 5 1/2" casing. Filled hole w/mud from 3395' back to 160' set a 15'
rock bridge and filled w/ ready mix cement back to zero 4' below ground level. 8 5/8"
surface pipe 4' below ground level.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 2/8/62

INV. NO. 4513-W