

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Company

Complete Address: Box 1070 Great Bend, Kansas

Lease Name Honderick Well No. 1

Location NW SE NE Sec. 10 Twp. 17 Rge. 17 (E) (W) XX

County Rush Total Depth 3609

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 4P Day 8 Month 1 Year 1969

The Above well was plugged as follows:

Total depth 3609' 8 5/8 csg set at 237' cwc 200 sk.

5 1/2 csg set at 3493 cw 150 sk cmt.

5 1/2 csg perf. 3366 5 1/2 csg DV tool set on anhy (1168) and cmt circ to surface (500 sk)

No Pipe Recovered

Pumped thru 5 1/2 plg container w/500 lbs hulls, 10 sk cmt., 30 sk gel, plug and 75 sk.

Cmt. Max. 2000 lbs. SI 2000 lbs.

Cmt.(0-600) gel(600-3200) Cmt & hulls(3200-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messinger
Well Plugging Supervisor

DATE 1/10/69
INV. NO. 9168-11