

KANSAS

JL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza Wichita, Kansas

Lease Name Gerboth Well No. 1

Location NE NW Sec. 9 Twp. 17 Rge. (E) (W) 17

County Rush Total Depth 3620'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 11 A Day 21 Month 7 Year 1970

The above well was plugged as follows:

Total Depth 3620' 8 5/8 csg set at 210' cwc 160 sk.

1/2 csg set at 3618' cw 200 sk cmt.

1/2 csg PBSD 3584' with top perf. (3478)

Filled 1/2 csg W/sd (3450-3584) Dumped 4 sk cmt W/dump bailer. (3400-3450)

Cutoff and recovered 2640' of 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/3 sk hulls, plug and 100 sk poz

W/6% gel. Max. pres. 400 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 7/24/70
INV. NO. 2278-W