

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC - 8 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-165-20,668 - CONSERVATION DIVISION  
Wichita, Kansas (this well)

Operator's Full Name Frontier Oil Co.  
Complete Address 1720 KSB&T Bldg., Wichita, Kansas  
Lease Name Crane "A" Well No. 1  
Location C S/2 NW Sec. 12 Twp. 17 Rge. (E) (W) 17  
County Rush Total Depth 3670'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Red Tiger Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 4 A Day 6 Month 12 Year 1977

The above well was plugged as follows:

RTD 3670' 8 5/8 csg set 254' cwc 165 sk. Plg. Mat. 50-50 poz 2% total gel.  
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.  
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey  
Well Plugging Supervisor

INVOICED  
DATE 12-8-77  
INV. NO. 6337-W